



DOUBLE BEAM BEARING ON COLUMN

INSTALLATION NOTE "A":

GROUT TUBE TO BE MATED WITH 3/4" ϕ ROD. TUBE TO BE FILLED WITH 6" MIN. SAND. REMAINING TO BE GROUTED WITH CEMENT.

for informational purpose only

